8. If the amount is not fully paid for by the purchaser before the dates fixed above, the initial deposit as well as the other moneys already paid in shall be forfeited to Government and all or any portion of the timber not fully paid for shall be resold at the risk of the purchaser in the manner prescribed for default of payment of one-tenth value in clause 5 *supra*.

9. No timber lot shall be permitted to be removed by the purchaser unless it has been paid for in full, calculated at the rates at which the timber is knocked down to him at the time of sale, excluding the ten per cent deposit paid for the lot at the time of the sale; and no timber shall be removed from the depot unless a permit is obtained from the Forest Officer in charge of the depot. The earnest money will not be adjusted towards the value of timber, until 90 per cent of the purchase money over and above the security deposit has been paid.

10. Timber purchased should be removed as early as possible, and in no case should it be allowed to remain longer than 90 days after the dates fixed in clause 7 *supra*. Timber not removed after purchase, will remain in the depot at the risk of the purchaser from the date of the confirmation of the sale.

11. If the timber is not removed within the time allowed, the same may, after ten days' notice to the purchaser, be sold in public auction and the proceeds will be given to the purchaser after defraying all the expenses in connection with the resale.

12. The deposit of Rs. 200 will remain as security for the due fulfilment of all and every one of the terms of sale, for the breach of any of which by the purchaser, the District Forest Officer shall be entitled to forfeit the deposit in whole or in part and in the event of such forfeiture, the sum so forfeited shall be immediately made good by the purchaser so long as the transaction is not finally closed. The security deposit or the balance thereof, if any, shall be returned to the purchaser after the full value of timber purchased has been paid for and the timber fully removed.

C. ABDUL JABBAR,
District Forest Officer.

CHITALDRUG DISTRICT.

Abstract Notification.

The attention of the public is invited to the detailed notification dated 29th December 1927, regarding the sale of timber in Harihar Timber Depot on the 20th January 1928, published on pages 2 and 3 in Part VI of the *Mysore Gazette*, dated 5th January 1928.

M. V. NARASIMHAIYA,
District Forest Officer.

ENGINEERING DEPARTMENT.

BANGALORE DIVISION.

Abstract Notification.

The attention of the public is invited to the notification published in pages 26 to 28 of Part VI of the *Mysore Gazette* dated 5th January 1928, calling for the tenders for the work of extending the Vani Vilas Institute at Bangalore.

Last date for the submission of tender 16th January 1928.

Abstract Notification.

The attention of the public is invited to the notice issued in pages 3 and 4 of Part VI of the *Mysore Gazette* dated the 5th January 1928, calling for the tender for the construction of a combined building for the Sub-Registrar's Office and Bonded Depot at Nelamangala.

Last date for the receipt of tenders is 16th January 1928.

R. W. SCALDWELL,
Executive Engineer.

KOLAR DIVISION.

Dated 7th Jauuary 1927.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M., on 9th February 1928, for restoring Surnahalli, Doddakere Minor Tank, R. No. 174 of Bowringpet Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1928.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

Description of work	Unit of work	Rate per unit

4. Each tender must be accompanied by a deposit of rupees three hundred and fifty (Rs. 350) in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Surnahalli Doddakere Minor Tank of Bowringpet Taluk" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The quotations should be noted in words as well as in figures.

Sl. No.	Items of work	Per	Quantity	Rate	Cost	Total
	Bund R. L. 54·50.			Rs. a. p.	Rs.	Rs.
1	Earthwork L. bund including watering and turfing.	C.yd.	6,752			
2	Turfing, ...	S.yd.	6,249			
3	Rough stone work new with jelly ...	C.yd.	1,458			
4	Do old do ...	,,	376			
5	Providing grade with index stones including cutting figures, etc., complete.	Each	25			
6	Providing B. M. stones	,,	2			
7	Providing Reg. No. and date stone ...	,,	1			
8	Jungle clearing	L. S.	..			
9	Providing jungle stones, complete ...	No.	1			
	Total ...	...	..	...	...	..
	Sluice R. L. 46·00.					
1	Constructing front and rear cisterns ...	L. S.	...			
2	Constructing masonery tunnel	R ft.	28			
	Total ...	...	...	...	...	...
	Waste weir 110' *R. L.* 50·00.					
1	Earthwork chargable to bund ...	C.yd.	202			
2	Burnt brick in surki mortar	C.ft.	904			
3	Burnt stone slabs	S.ft.	141			
4	Plastering with surki mortar	Sqr.	8·42			
5	Rough stone work, new	C.yd.	116			
6	Providing joggles	L. S.	...			
	Total ...	...	...	...	...	...
	Contingencies at five per cent ...	...	...	...	...	..
	Grand Total ...	...	...	..	...	...

Notice dated 7th January 1928.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kolar Division up to 2 P.M., on 2nd February 1928, for maintenance work of Somambudhi Agrahar Tank, Kolar Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1928.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompained by a statement in the form given below, showing the rates at which the different items specified will be executed :—

Description of work	Unit of work	Rate per unit

4. Each tender must be accompanied by a deposit of Rs. 350 in cash or Government Promissory Notes, as earnest money and be superscribed "Tender for maintenance work of Somambudhi Agrahar Tank, Kolar Taluk, in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The quotations should be noted in words as well as in figures.

Items of work	Per	Quantity	Rate	Cost	Total
			Rs. a. p.	Rs.	Rs.
Earthwork to bund including watering and tamping etc.	C.yd.	14,423			
Turfing to slope	S.yd.	29,182			
Jungle clearing	Grade	63			
Total ...	...	...			

Dated 7th January 1928.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kolar Division, up to 2 P.M., on 8th February 1928, for restoring Guddanahalli Kodagikere Minor Tank R. No. 490 of Malur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1928.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

Description of work	Unit of work	Rate per unit

4. Each tender must be accompanied by a deposit of Rs. 400 in cash or Government Promissory Notes, as earnest money and be superscribed "Tender for restoring Guddanhalli, Kodagikere Minor Tank, Malur Taluk, in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The quotations should be noted in words as well as in figures.

Items of work	Per	Quantity	Rate	Cost
			Rs.	Rs.
BUND.				
Clearing jungle	Grade	14		
Cutting grips to old bund	,,	14		
Earthwork to bund including watering and tamping ...	C.yd.	697		
Carting earth from weir with watering and tamping ...	,,	4379		
Turfing	S.yd.	4926		
Resetting old stone revet with new jelly	C.yd.	461		
New stonework	,,	869		
Preparing and fixing new grade stones	Each	23		
Do index stones	,,	23		
Do B. M. stones	,,	2		
Do Reg. No. stone	,,	1		
Do gauge stone	,,	1		
Total Bund ..	...	...		
SLUICE.				
Earthwork excavation	C.yd.	49		
Do refilling with watering and tamping ...	,,	54		
Concrete in surki mortar	C.ft.	364		
Burnt brick in surki mortar	,,	246		
Surki mortar plastering	Sqr.	4·14		
Burnt stone slabs 6" thick	S.ft.	241		
Drilling holes in orifice	L. S.			
Providing plug and rod with locking arrangement etc..	,,			
Total Sluice ...	..	...		
WEIR.				
Earthwork excavation	C.yd.	4379		
Concrete in surki mortar	C.ft.	604		
Burnt brick in surki mortar	,,	2556		
Burnt stone slabs 6" thick	S.ft.	571		
Surki mortar plastering	Sqr.	31·32		
New stone work	C.yd.	873		
Tongue and grove joints	No.	72		
Joggle joints with stone joggles etc. complete ...	No.	26		
Total Weir ...	...	..		
Contingencies ..	...	..		
Grand Total ...	...	...		

N. G. KRISHNA IYENGAR,
Executive Engineer.